



**NOTES:**

- CABLE AND LIGHTNING ARRESTOR SUPPLIED BY BELL CANADA.
- ROUTER, DSL MODEM AND MEDIA CONVERTOR SUPPLIED BY REGION.
- ALL WIRING TO BE DONE TO TIA568B WIRING MAP.
- BIX BLOCKS TO BE SUPPLIED BY THE CONTRACTOR. FOR OUTDOOR SITES, BIX BLOCKS MAY BE INSIDE THE PANEL ENCLOSURE.
- REFERENCE DRAWINGS E809 FOR THE LOCATION OF THE BIX BLOCK, LIGHTNING PROTECTION AND GROUND LUG FOR OUTDOOR STATIONS.

THESE DRAWINGS ARE TEMPLATE DRAWINGS

- REMOVE THIS NOTE AS PART OF THE DESIGN PROCESS.
- MODIFY THIS DRAWING AS DIRECTED IN THE SCADA STANDARDS.
- ADD ADDITIONAL DETAILS AS REQUIRED TO MEET THE PROJECT SPECIAL REQUIREMENTS.
- WHEN THE CONSULTANT DEVIATES FROM THIS TEMPLATE THEY ARE REQUIRED TO NOTIFY HALTON REGION THROUGH THE USE OF THE STANDARDS DEVIATION MEMO.
- FUSED TERMINAL BLOCKS AND CIRCUIT BREAKERS TO BE SIZED APPROPRIATELY.
- SHOW ADDITIONAL TWO RACKS.

NO	Date	By	REVISIONS	MANUAL CAD
Design	---	Ch'kd	---	Date
Drawn	---	Ch'kd	---	References
Scale	N.T.S.			

Field Notes

Stamp

Regional

ACCEPTED FOR CONSTRUCTION OF REGIONAL INFRASTRUCTURE

REVIEWED FOR COMPLIANCE WITH REGIONAL STANDARDS ONLY.

Director, Water & Wastewater Treatment

Manager, Plant Capital & Engineering

**TITLE** REGIONAL MUNICIPALITY OF HALTON CONSULTANT PROJECT TITLE

TYPE II, III, IV WWPS NETWORK

Consultant File NO	Regional Drawing NO
---	---
CONTRACT NO	Drawing NO 1920
---	SHEET XX OF XX